

## VHX-66F-BRO

Dakota Digital VHX Instrument Installation For 1966-'77 Ford Bronco

Your new VHX-66F-BRO kit should include:



**Universal Sender Installation Manuals** Pack VHX







**Ford Speed** Sender

**Switch Assembly** 

**CAT5 Cable** 

## Installation

1. Remove the stock gauges from the dash. Remove the four screws holding the gauges cluster to the dash. These screws will be re-used for the VHX installation.




2. Remove these four screws to separate the bezel from the gauges and set aside for reassembly.



3. Remove the gauges, separator plate, and lens. The only part that will be re-used is the stamped bezel and the screws that mount the bezel. Now is a good time to clean the bezel.





5. Secure the VHX system to the bezel with the four screws from disassembly. The VHX system should align tightly and sit flush with the bezel.



6. Connect the CAT5 cable to the system so it can be routed and connected to the control box as the system is re-installed



7. Install system with original bezel back into the dash with the four original screws and refer to the main manual for wiring instructions to complete the VHX installation.



▲ WARNING: This product can expose you to chemicals including lead, which is known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to <a href="https://www.P65Warnings.ca.gov">www.P65Warnings.ca.gov</a>



4510 W. 61st St. North Sioux Falls, SD 57107 www.dakotadigital.com

Phone (605) 332-6513 Fax (605) 339-4106

dakotasupport@dakotadigital.com Copyright 2011 - Dakota Digital, Inc.